

Addendum #2
Answers to Bid Questions Meadowview Drainage Project.
January 14, 2022

1. What side of 75 West is the pipe to be installed.
The pipe is to be installed on the West side of 75 West. With the approval of the owner 75 West may be crossed for a better installation.
2. In Article 7 of the Bid Form Item G stated Exhibit B Wage and Fringe Benefit Certification to be attached to the bid. There is no exhibit B included in the spec manual and this was not mentioned in Addendum #1. Will you be providing this.
There is no wage and fringe benefit certification required for this job.
3. On the #8 & #53 agg, what type of agg is to be used? INDOT crushed concrete, INDOT slag or INDOT Limestone?
The County has approved and used all 3 types mentioned.
4. Plans show riprap and fabric at the outlet. Where are we to include this cost? Quantity of each.
Include all costs for the Outlet to Kingsbury Ditch in item 14.
5. Are we required to install silt fence along the 30" HDPE route as its not shown on the plans.
A silt fence will not be required along 75 W.
6. How far is the proposed pipe from the edge of asphalt?
To keep from damaging the road the edge of trench would need to be 5 ft. from the edge of the road shoulder. The pipe will need to stay in the ROW and miss the utilities.