

Spec Sheet for La Porte County Fair Ag Association New Building Electric

LaPorte County Fair Ag Association is providing ALL material-Must provide Material List

RFI due to the Fair Office by January 8th at 3pm.

Bids due to the Fair Office by January 15th at 3pm.

Material List must be provided with the bid.

Start after bid awarded

Completed by May 15, 2025

Scope of Work

Furnish labor only to perform the following electrical scope at the La Porte County Fairgrounds.

1. Cost of Permit will be waived but County Permit must be pulled.
2. Trench and backfill for 800-amp feed from existing transformer to new 124'x224' building
3. Install four (4) conduits in trench.
4. Pull 200-amp circuits in each of the four (4) conduits.
5. Four (4) 200-amp, MCB electrical panels with eight (8) circuit capacity.
6. Four (4) 200-amp, MLO electrical panels with forty (40) circuit capacity.
7. 200-amp wire between MCB & MLO panels.
8. 200-amp conduit for the four (4) 200-amp feeds.
9. Two (2) exit lights.
10. Eight (8) emergency lights.
11. One hundred eighty-nine (189) duplex receptacles of which seventy-eight (78) will be GFCI. They need to be 20 amp commercial grade.
12. Grounding for all electrical panels.
13. Eighteen (18) outdoor wall packs.
14. Six (6) canopy lights.
15. Eighty-four (84) hi-bay light fixtures.
16. Four (4) roof cupola fans and associated controls.
17. Four (4) outdoor GFCI receptacles.
18. Electrical terminations at transformer.
19. Scissor lift rental for one month.
20. Built to Building Code
21. All conduit to be ran overhead except feed from transformer
22. Six (6) 50-amp plugs-one at each corner and One on the outside by each Center overhead doors.
23. All Conduit, no romex

Please Contact the Fair Office for Information or to schedule a Walk Thru of the Building.
219-362-2647 or laportefair@gmail.com